

SUMMARY: ASBESTOS DISPOSAL SITE PROJECT REQUIREMENTS PURSUANT TO Env-Sw 2100 & Env-A 1800

PROJECT TYPE (REF. ENV-A 1800 AND ENV-SW 2105.04)	WORKER CREDENTIALS (REF. ENV-A 1800)	WORK PLAN REQUIREMENTS (REF. ENV-SW 2106)	PROJECT COMMENCEMENT NOTIFICATION REQUIREMENTS (REF. ENV-SW 2105.07)	REPORTING REQUIREMENTS (REF. ENV-SW 2105.16 & ENV-SW 2105.17)
--	---	---	---	--

Minor Projects <i>quantity disturbed ≤ 1 m³ or 15 m²; (ref. Env-Wm 3902.09)</i>				
Emergency Projects, per Env-Sw 2102.06	Person performing work must: <ul style="list-style-type: none"> ▪ be competent/qualified (see Env-Sw 2102.11) ▪ be trained and certified per Env-A 1812, unless the work is a license-exempt small scale/short duration project¹ or license-exempt surface scrap removal project². (Note: the number of certified experienced workers at the site must equal or exceed the number of certified workers-in-training). ▪ work under a licensed entity or individual, unless the work is a license-exempt small scale/short duration project, license-exempt surface scrap removal project, or license-exempt single family homeowner self-implemented project³ 	No written work plan required	<u>Who:</u> <ul style="list-style-type: none"> ▪ Local Health Officer ▪ NH Dept. of Environmental Services, Air Division ▪ <u>How & When:</u> Verbal notice as soon as practicable under the circumstances, followed within 48 hours by written confirmation <u>Exceptions:</u> <ul style="list-style-type: none"> ▪ For license-exempt small scale/short duration projects, notify the Local Health Officer before starting the work (ref. Env-A 1811). ▪ For license-exempt surface scrap removal projects, there is no notice requirement. 	<ul style="list-style-type: none"> ▪ Site owner must maintain complete project records. ▪ If disposal area is reconfigured, submit as-built drawing to DES-Waste within 60 days of project completion. ▪ Maintain waste shipment records per 40 CFR 61 & 49 CFR 171-172.
Non-Emergency Projects			<u>Who:</u> <ul style="list-style-type: none"> ▪ Local Health Officer ▪ NH Dept. of Environmental Services, Air Division (DES-Air) <u>How & When:</u> Verbal or written notice as soon as practicable after knowing work involves asbestos. If verbal, provide written notice within 48 hours thereafter	
Major Projects <i>quantity disturbed >1 m³ or 15 m² (ref. Env-Wm 3902.08)</i>				
Emergency Projects, per Env-Sw 2102.06	Person performing work must: <ul style="list-style-type: none"> ▪ be competent/qualified (see Env-Sw 2102.11). ▪ be trained and certified per Env-A 1812, unless the work is a license exempt surface scrap removal project. (Note: the number of certified experienced workers at the site must equal or exceed the number of certified workers-in-training). ▪ work under a licensed entity or individual, unless the work is a license-exempt surface scrap removal project, or license-exempt single family homeowner self-implemented project. 	No written work plan required	<u>Who:</u> <ul style="list-style-type: none"> ▪ Local Health Officer ▪ NH Dept. of Environmental Services, Air Division (DES-Air) ▪ NH Dept. of Environmental Services, Waste Division (DES-Waste) <u>How & When:</u> Verbal notice as soon as practicable under the circumstances, followed within 48 hours by written confirmation	<ul style="list-style-type: none"> ▪ Site owner must maintain complete project records. ▪ If disposal area is reconfigured, submit as-built drawing to DES-Waste within 60 days of project completion. ▪ Maintain waste shipment records per 40 CFR 61 & 49 CFR 171-172.
Non-Emergency Projects		Approved, written work plan required, except for license-exempt surface scrap removal projects.	<u>Who:</u> <ul style="list-style-type: none"> ▪ Local Health Officer ▪ NH Dept. of Environmental Services, Air Division (DES-Air) ▪ NH Dept. of Environmental Services, Waste Division (DES-Waste) <u>How & When:</u> As specified in approved work plan. If a generic work plan, the recommended provisions are to provide verbal or written notice as soon as practicable after knowing work involves asbestos. If such notice is given verbally, provide written notice within 48 hours thereafter	<ul style="list-style-type: none"> ▪ If project takes over 2 weeks, submit weekly progress reports to DES-Waste and local health officer. ▪ Within 60 days of completion, submit project completion report to DES-Waste and Local Health Officer.

¹ License-exempt small scale/short duration projects involve the disturbance of less than one cubic foot and 3 square feet of asbestos waste, completed within 2 hours of being initiated. The work can not be part of a larger project that is being segmented into several small scale, short duration tasks. See Env-A 1811.03(c) for additional detail.

² License-exempt surface scrap removal projects involve the removal of non-friable asbestos ONLY from the ground surface to a container for disposal at an authorized facility in accordance with Env-Sw 2101. The work does not involve excavation below the ground surface or contact with friable asbestos. See Env-A 1811.03(d)

³ License-exempt homeowner self-implemented projects involve the disturbance of an asbestos disposal site by the owner of a single-family, owner occupied residence, on the property where that residence is located. See Env-A 1811.03(b). Note: The property owner is exempt from having to work under the authority of a license, but is NOT exempt from having to be trained and certified pursuant to Env-A 1812.

rev. date: 06-23-09