# New Hampshire Stormwater Manual

## VOLUME 3
## Erosion and Sediment Controls During Construction

December 2008

United States Environmental Protection Agency

New Hampshire Department of Environmental Services

Comprehensive Environmental Inc.

**NEW HAMPSHIRE STORMWATER MANUAL**

VOLUME 3
Erosion and Sediment Controls During Construction

**Written, Compiled and Edited**
by Comprehensive Environmental Inc.
and the New Hampshire Department of Environmental Services

The compilation of this document was drawn extensively from the following sources, as well as other references cited in the text:

Hubert, M (Eds.). (March 2003). *Maine Erosion and Sediment Control BMPs*. Augusta, ME: Bureau of Land and Water Quality, Maine Department of Environmental Protection (ME DEP). Accessed May 2007: http://maine.gov/dep/blwq/docstand/escbmps/index.htm

Minnick, E.L. and H.T. Marshall. (August 1992). *Stormwater Management and Erosion and Sediment Control Handbook for Urban and Developing Areas in New Hampshire*. Exeter, NH: Rockingham County Conservation District.

Rothchild, J.A. (Eds.). (2001). *2002 Connecticut Guidelines for Soil Erosion and Sediment Control*. Hartford, CT: Connecticut Department of Environmental Protection.

Salix, Applied Earthcare. (2004). *Erosion Draw 5.0: Erosion Control Standards and Construction Drawings*. Redding, CA: Salix, Applied Earthcare.

**Design and Layout**
by Comprehensive Environmental Inc.

**Illustrations** adapted from cited reference material.

**Photography** by New Hampshire Department of Environmental Services

**Cover Photograph** by David Price, New Hampshire Department of Environmental Services.
Development of a residential community in Exeter, NH.

WD-08-20C

# NEW HAMPSHIRE STORMWATER MANUAL

## VOLUME 3
## Erosion and Sediment Controls During Construction

December 2008
Revision 1.0

Thomas S. Burack, *Commissioner*

Michael J. Walls, *Assistant Commissioner*

Harry Stewart, P.E., *Director, Water Division*

This manual is funded in part through a
Clean Water Act Section 319
Nonpoint Source Program grant and a
Clean Water Act Section 104(b)(3) grant from the U.S.
Environmental Protection Agency through the
New Hampshire Department of
Environmental Services,
Watershed Assistance Section.

Printed on Recycled Paper

# Acknowledgements

To the individuals who assisted in the creation of this manual, a special thank you for your time, commitment, and support, and for your dedication to the protection of New Hampshire's environment.

## NHDES Project Team

Amy C. Clark, P.E., *NHDES Terrain Alteration Bureau*
Gregg Comstock, P.E., *NHDES Water Quality Section*
Paul Currier, P.E., *NHDES Watershed Management Bureau*
Ridgely Mauck, P.E., *NHDES Terrain Alteration Bureau*
Jillian McCarthy, *NHDES Watershed Assistance Section*
Eric Williams, *NHDES Watershed Assistance Section*

## Provided Support and Assistance

Laura Aibel, *City of Concord, NH*
Arlene Allen, *NHDES Wetlands Bureau*
Jeffrey G. Andrews, P.E., *NHDES Wastewater Engineering Bureau*
Bill Arcieri, CPESC, *Vanasse Hangen Brustlin, Inc.*
Richard G. Ball, *Town of Belmont, NH*
Sara Carbonneau, *Town of Swanzey, NH*
Alicia Carlson, *NHDES Drinking Water and Groundwater Bureau*
Jeffrey K. Clifford, P.E., *Altus Engineering, Inc.*
Karen H. Dudley, CPSC, *Natural Resources Conservation Services*
Darlene Forst, *NHDES Wetlands Bureau*
James P. Gove, CSS, CWS, CPSC, CPESC, *Gove Environmental Services, Inc.*
Tony Marcotte, P.E., *MDP Development, Inc.*
Kevin A. McCaffery, P.E., *Stantec*
Tyler Phillips, CPESC, *Horizons Engineering*
Michael J. Redding, P.E., CPESC, *GeoInsight, Inc.*
Pierce Rigrod, *NHDES Drinking Water and Groundwater Bureau*
Robert Roseen, P.E., Ph.D., *University of New Hampshire*
Randall Shuey, CPESC, *New England Environmental, Inc.*
Gary Springs, CPESC, *Certified Erosion Control – NH*
J. Daniel Tatem, *Stantec*

## Project Team at Comprehensive Environmental, Inc.

Rebecca Balke, P.E., Senior Engineer
Julia Capurso, E.I.T., Project Engineer
David Nyman, P.E., Project Manager
Eileen Pannetier, Program Director

# Table of Contents


**Chapter 1 Introduction** ..... 1

**1-1. About the New Hampshire Stormwater Manual** ..... 2

**1-2. About Volume 3** ..... 4

**Chapter 2 Regulation & Permitting** ..... 7

**2-1. New Hampshire Regulatory Programs** ..... 9

NH Statutes ..... 9

NH Surface Water Quality Regulations ..... 9

401 Water Quality Certification ..... 9

NH Alteration of Terrain Permit ..... 10

NHDES Wetlands Bureau Dredge and Fill Permit ..... 11

NHDES Shoreland Permit ..... 12

**2-2. Federal Permit Programs** ..... 13

National Pollutant Discharge Elimination System Program ..... 13

Department of the Army Programmatic General Permit - State of New Hampshire ..... 15

**Chapter 3 Planning & Selecting Erosion & Sediment Controls** ..... 17

**3-1. Erosion and Sediment Control Strategies** ..... 17

**3-2. The Erosion and Sediment Control Plan** ..... 23

Erosion and Sediment Control Plan Narrative ..... 24

Erosion and Sediment Control Drawings ..... 25

**3-3. Erosion and Sediment Control Selection Table** ..... 28

**Chapter 4 Construction Phase Erosion & Sediment Controls** ..... 30

**4-1. Erosion Control Practices** ..... 31

Construction Phasing ..... 32

Dust Control ..... 38

Surface Roughening ..... 42

Soil Stockpile Practices ..... 46

Temporary & Permanent Mulching ..... 48

Temporary Vegetation ..... 54

Permanent Vegetation ..... 60
Temporary Erosion Control Blanket ..... 68
Diversion ..... 76
Slope Drain ..... 82
**4-2. Sediment Control Practices ..... 89**
Silt Fence ..... 90
Straw or Hay Bale Barrier ..... 100
Erosion Control Mix Berms ..... 106
Temporary Check Dams ..... 114
Temporary Storm Drain Inlet Protection ..... 118
Temporary Construction Exit ..... 124
Temporary Sediment Trap ..... 128
Temporary Sediment Basin ..... 138
Construction Dewatering ..... 144
Flocculants ..... 150
**4-3. Winter Weather Stabilization & Construction Practices ..... 152**
**4-4. Erosion and Sediment Control Monitoring ..... 156**
Inspection of Erosion and Sediment Controls ..... 156
Contingency Measures During Construction ..... 158

**Appendix A. References ..... 159**

**Appendix B. Sample Inspection Report ..... 161**

## List of Tables

Table 3-1. Selection of
Erosion and Sediment Control Practices.....29
Table 4-1. Seeding Recommendations
for Temporary Vegetation.....58
Table 4-2. Seed Mixture Selection Based on Soil Type.....65
Table 4-3. Seed Mixtures for Permanent Vegetation .....66

## List of Figures

Figure 2-1. Applicability of Permit Programs.....8